BRUHATH BANGALORE MAHANAGARA PALIKE,DASARAHALLY ZONE

Office of Executive Engineer Dasarahalli Division

Shedule -B

Name of work : Improvements works to storm water drain in Bagalagunte ward no.14

Sl No	Discription of work	Unit	Quantity	Sanctioned Rate	
				In Figure (Rs.)	In word
1	Exacavationand Removel of silt and silt mix sand Slushy Condtion from canel bed Including disposal of the same in spoil bank or On canal emabanckment in layers as Diriected ets. Complete with Incial lead upto 50 Mt Complete as per specification and Diriection of Engineer Incharge	Cum	4320.00	201.97	
2	Disposal of desries to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 km a) basic rate for haulage of materilas as per item no 17.4/KSRRB : M 100.4.1... Rs 2.00 Tonne/KM b) Average earth of work 1.28 Tonne/KM for Rs 2.0/km c) Add loading and unloading Complete as per specification and Diriection of Engineer Incharge	Cum	4063.50	70.29	
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications Complete as per specification and	Sqm	99.00	352.45	
4	Providing and laying in position plain/Reinforced cement cement concrete M20 for sub-structure/Superstructure works, with cement @ 320 kgs, 20 mm & down size graded granite metal coarse aggregate @ 0.69 cum and fine aggregates @ 0.46 cum machine mixed with super plasticisers @ 3 lts confirming to IS 9103-2008,concrete laid in layers, well compacted and providing weep holes wherever necessary. with necessary scaffolding, form work etc., including cost of labour, HOM curing etc., complete. Complete as per specification and Diriection of Engineer Incharge	Cum	49.50	5013.85	
5	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification Complete as per specification and Diriection of Engineer Incharge	Tone	4.95	68710.63	

Scanned by CamScanner

6	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials - Data rate approved by Chief Engineer, Dasarahalli zone	Sqm	110.00	2097.60	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner